



पी0 एन0 जी0, राजकीय स्नातकोत्तर महाविद्यालय, रामनगर
नैनीताल (उत्तराखण्ड)

Email- principal_pngrmr@yahoo.co.in

Web add- www.gpgcramnagar.org


पत्रांक- S3 /प्रागण/2026-27

दिनांक-21.04.2026

कोटेशन सूचना

सत्र 2026-27 के लिए महाविद्यालय में ओपन एयर थियेटर के समीप अवस्थित महिला शौचालय की मरम्मत एवं उच्चीकरण के कार्य हेतु पंजीकृत फर्मों/ठेकेदारों से दिनांक-30.04.2026 के अपराह्न 4:00 बजे तक स्पीड पोस्ट द्वारा कोटेशन निर्धारित प्रारूप में आमंत्रित किये जाते हैं। जिसे दिनांक 01.05.2026 को अपराह्न 2:00 बजे महाविद्यालय के कार्यालय में खोले जायेंगे। कार्य आदि के विवरण की जानकारी कार्यालय से किसी भी कार्य दिवस को प्रातः 10:00 बजे से सांय 4:00 बजे तक प्राप्त की जा सकती है। कोटेशन खोलने के तिथि में अवकाश होने पर अगले कार्य दिवस में खोले जायेंगे।

| क्र० सं० | कार्य का नाम | दर प्राप्त करने की तिथि |
|----------|---|-------------------------|
| 01 | ओपन एयर थियेटर के समीप अवस्थित महिला शौचालय की मरम्मत एवं उच्चीकरण का कार्य | 30.04.2026 |


प्राचार्य
राजकीय स्नातकोत्तर महाविद्यालय
रामनगर, नैनीताल

प्रतिलिपि सूचनार्थ और वृहद प्रचारार्थ चस्पा करने हेतु-

1. तहसील कार्यालय के सूचना पट्ट में
2. डा0 दीपक खाती को उक्त सूचना वेबसाइट में अपलोड करने के संबंध में।
3. महाविद्यालय के सूचना पट्ट में।

प्राचार्य
राजकीय स्नातकोत्तर महाविद्यालय
रामनगर, नैनीताल



पी0 एन0 जी0, राजकीय स्नातकोत्तर महाविद्यालय, रामनगर
नैनीताल (उत्तराखण्ड)

Email- principal_pngrmr@yahoo.co.in

Web add- www.gpgcramnagar.org

FORMAT

Name of work -The Regarding Toilet Repairing Work in collage Campus, Ramnagar,
(Nainital)

| Sl. No | Details of Work and particulars | Qty. | Unit | Rate | Per | Amount |
|--------|--|--------|-------|------|-----|--------|
| 1. | Dismantling / Removal tile work in floors and roofs laid in cement mortar including stacking material within 50 meters lead. For thickness of tiles 10 mm to 25 mm. | 35.75 | Sq.m | | | |
| 2. | Rerouting of the main water supply line from the exterior to the interior | 28.90 | Sq.m | | | |
| 3. | Providing and fixing white vitreous china water closet squatting pan (Indian type) : Orissa pattern W.C. pan of size 580 mm | 06 | Piece | | | |
| 4. | Providing and fixing controlled flush, low level cistern made of vitreous china with all fittings complete. | 06 | Piece | | | |
| 5. | Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore. | 07 | Piece | | | |
| 6. | Providing and fixing C.P. brass long body bib cock / faucets of approved quality conforming to IS standards and weighing not less than 690 gms.:15 mm nominal bore | 06 | Piece | | | |
| 7. | Providing and fixing wash basin with C.I. brackets, 15 mm dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required:- White Vitreous China Wash basin size 550x400 mm with a 15 mm CP Brass single hole basin mixer | 01 | Piece | | | |
| 8. | Installation of a faucet (jaquar brand or Somany brand) | 01 | Piece | | | |
| 9. | Providing and fixing unplasticized PVC connection pipe with brass unions : 60 cm length. 20 mm nominal bore. | 07 | Piece | | | |
| 10. | Providing and laying ceramic glazed floor tiles of size 300x300 mm (Thickness to be specified by the manufacturer) of 1 st quality conforming to 15:15622 of approved make in colours such as white, luory, gray, fine red brown, laid on 20 mm thickness cement mortar 1:4 (1 cement:4 coarse sand) Joint with grey cement slurry @ 3.3 kg./Sqm including painting the joints with cement and matching pigment etc. complete | 143.81 | Sq.m | | | |
| 11. | 62 mm thick cement concrete flooring with concrete hardener topping, under layer 50 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone | 19.08 | Cu.m | | | |

| | | | | | | |
|-------|---|-------|-------|--|--|--|
| | aggregate 6 mm nominal size) by volume, hardening compound mixed @ 2 liter per 50 kg of cement or as per manufacturer's specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete. | | | | | |
| 12. | Providing and fixing of outside parking tiles (2.40 x 1.35 Sq.m) | 03.24 | Sq.m | | | |
| 13. | 12 mm cement cailling plaster of mix : 1:4 (1 cement: 4 fine sand) Interior and Exterior plastering of walls size -(01.64+12.22=13.86) | 13.86 | Sq.m | | | |
| 14. | Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats overand including priming coat of exterior primer applied @ 0.90ltr/ 10 sqm. | 18.92 | Sq.m | | | |
| 15. | Providing and wiring for light point with 1.5 Sq. mm FRLS P.V.C. insulated copper conductor single core cable in recessed P.V.C. flaxibol pipe. With modular switch, modular socket, modular plate etc along with 1 no 1.5 Sq. mm P.V.C. insulated copper conductor single core cable for loop Earthing As required.Complete in all respects. | 08.00 | Point | | | |
| 16. | Steel work welded in build up section/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar work. | 165.0 | Kg. | | | |
| 17. | Crazy marble stone flooring, including filling the gaps with light shade pigment with white cement marble power mixture (3 parts of white cement: 1 part of marble power) by weight in proportion of 4:7 (4 cement marble power mix : 7 white, black or white and black marble chips sizes from 1 mm to 4 mm nominal size by volume) with under layer 25 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) including rubbing, polishing and cement slurry etc. 18 mm thick crazy marble stone white, black or as specified. | 1.14 | Sq.m | | | |
| GST | | | | | | |
| Total | | | | | | |

